

Appendix 1 Emerging Technologies Exceptions

For **Micro-generators** classified as an emerging technology at the time of the network, in accordance with the procedures set out in Title VI of EU Net for Grid Connection of Generators the following sections of this document

- The interface protection settings in 9.1.3
- The rate of change withstand capability in 8
- The rate of change of frequency in 9.4
- The limited frequency sensitive mode – overfrequency in 9.5
- The constant active power output in 9.6

Performance settings for these emerging technologies will be within the Table AP1 and this does not mean they have to extend to the full ranges requirements. For example if a technology can only operate in a frequency range of 47.5 Hz and outside of this it will disconnect from the Distribution Network, this is deemed to meet this **EREC G98-2**.

Table AP1 Protection Settings for **Micro-generators** Emerging technologies

Protection Function	Trip Setting	Tripping Time
U/V stage 1	$V_{\phi-n^{\dagger}} - 13\% = 200.1V$	2.0s
U/V stage 2	$V_{\phi-n^{\dagger}} - 20\% = 184V$	0.1s
O/V stage 1	$V_{\phi-n^{\dagger}} + 14\% = 262.2V$	1.0s
O/V stage 2	$V_{\phi-n^{\dagger}} + 19\% = 273.7V^1$	0.1s
U/F stage 1	47.5Hz	20s
U/F stage 2	47Hz	0.1s
O/F stage 1	51.5Hz	90s
O/F stage 2	52 Hz	0.1s
Loss of Mains*	12 degrees	0.1s

Micro-generators classified as emerging technologies and connected to the grid prior to the date of revocation of that classification as an emerging technology are still existing.

Micro-generators classed as emerging technology are:


TO BE ADDED with ENA

Appendix 2 Connection Procedure Flow Chart

Connection Procedure Flow Chart - For multiple **Micro-generating Plants** in the same **Close Geographic Region** made up of **Type Tested Micro-generators** and **Type Tested Micro-generating Units** with a rated capacity of less than 16 A per phase with an aggregate rated capacity of less than 17 kW 3 phase; per customer installation. For single **Micro-generating Plants** or **Micro-generating Units** see the current version of **EREC G98-1**. For installations with aggregate capacity >16 A per phase and <50 kW 3 phase or using non **Type Tested** equipment see the current version of **EREC G98-1**.

NOTE: The processes shown here only refer to the interface between the **Installer/ User** and the **DNO**. It may also be necessary for the **Installer/ User** to inform the relevant **DNO** that a **Micro-generator** has been installed.

Connecting Type Tested Micro-generator(s) in multiple premises
Generating Unit(s) >16 A per phase and <50 kW 3 phase in single phase



Appendix 3a Application for Connection of multiple Micro-generators

Application for connection of multiple Micro-generating

To	ABC electricity distribution	DNO contact
	99 West St, Imaginary Town, ZZ99 9AA	abcd@wxy

Installer Details:

Installer	
Accreditation / Qualification	
Address	
Post Code	
Contact person	
Telephone Number	
E-mail address	

User Details:

User (name)	
Address	

Use continuation sheet where more than 10 Micro-generating Units are to be installed.

Please include an electronic map with the location of each property highlighted in red.

Record Micro-generating Unit capacities, in rated output kW at 230V AC, to one decimal place for single phase supplies and under the relevant phase for two and three phase supplies.

Detail on a separate sheet if there are any proposals to limit export to a lower figure than the rated output of the generating Units.

**Appendix 3b. Application for connection of Type Tested Generating Unit with
 aggregate Power Station capacity <50kW 3 phase or 17kW single phase**

Application for Connection of Type Tested Generating Unit with Aggregate Capacity < 50 kW 3 - Phase, or <17 kW Single Phase		
To	ABC electricity distribution 99 West St, Imaginary Town, ZZ99 9AA	DNO or IDN abcd@wxy
Installer Details:		
Installer		
Accreditation / Qualification		
Address		
Post Code		
Contact person		
Telephone Number		
E-mail address		
User Details:		
User (name)		
Address		
Post Code		
Contact person (if		

Balance of Multiple Single Phase Generating Units – where applica

I confirm that design of the complete installation has been carried out to to below 16 A per phase, as required by **EREC G98-2**

Signed:

Date:

Appendix 4a Installation Document

The following form needs to be provided for every **Generating Unit**

Installation Document for Generating Units EREC G98-2		
Please complete and provide this document for every Generating Unit . Generating Units will exist within one premise once installation is complete. Provide an "Installation cover" form also. For example, if three Generating Units are at one location then three Installation documents plus an "Installation cover" form are required.		
To	ABC electricity distribution 99 West St, Imaginary Town, ZZ99 9AA	DNO or IDNO abcd@wxyz.com
Installation details		
Address		
Including Post code		
Location within Customer's Installation		
Location of Lockable Isolation Switch		
Date of connection		
Primary energy source		
Type tested reference number		
Classification if an emerging technology		
Maximum installed capacity in kW	3 Phase	PH 1
User contact details		
Name		
Address		

Generating Unit Type Test Reference Number,² or for **Generating Units** listed on the ENA web site a completed **Generating Unit Type Test Sheet** Schedule of protection settings (may be included in circuit diagram)

Commissioning Checks Micro-generating Plants should leave this sheet for **Type Tested Generating Units** greater than 16 A per phase with an output power greater than 17 kW per phase or 50 kW three phase; per **Customer's installation**

Installation satisfies the requirements of BS7671 (IET Wiring Regulations) Suitable lockable points of isolation have been provided between the **Generating Units** and the rest of the installation.

Labels have been installed at all points of isolation in accordance with **EN 60445**

Interlocking that prevents **Generating Units** being connected in parallel with the **DNO** system (without synchronising) is in place and operates correctly.

The **Interface Protection** settings have been checked and comply with **BS 7671** **Generating Units** successfully synchronise with the **DNO** system without causing significant voltage disturbance.

Generating Units successfully run in parallel with the **DNO** system without causing significant voltage disturbances.

Generating Units successfully disconnect without causing a significant voltage disturbance, when they are shut down.

Interface Protection operates and disconnects the **Generating Units** (within 1s) when a suitably rated switch, located between the **Generating Units** and the **DNOs** incoming connection, is opened.

Generating Unit(s) remain disconnected for at least 20s after switch is re-closed.

Loss of tripping and auxiliary supplies Where applicable, loss of supply to tripping and protection relays results in either **Generating Unit** lockout or a 24hr manned control centre.

Balance of Multiple Single Phase Generating Units Confirm that design and complete installation has been carried out to limit output power imbalance to 16 A per phase, as required by **EREC G98-2**

Appendix 4b Installation Cover

This form should be submitted with all **installation documents** for each

Installation cover	
Please complete and provide this document for every site where a Generating Unit is installed. Where multiple Generating Units will exist within one premise once installed, you must provide Installation documents for each also. For example, if three Generating Units are installed in a single location then three Installation documents plus this form must be provided.	
To	ABC electricity distribution 99 West St, Imaginary Town, ZZ99 9AA
	DNO or IDNO abcd@wxyz.com
User contact details	
Name	
Address	
Including Postcode	
Telephone number	
Email address	
Installer contact details	
Name	
Accreditation/ qualification	
Address	
Including Postcode	
Telephone number	
Email address	
Installation details	

Appendix 5 Type Test Sheet / verification report

Type Approval and manufacturer/supplier declaration of compliance of EREC G98-2 .			
Type Tested reference number			
Generating Unit technology			
System Supplier name			
Address			
Tel		Fax	
E:mail		Web site	
Maximum rated capacity, use separate sheet if more than one connection option.	Connection Options		
		kW single phase, single, s	
		kW three phase	
		kW two phases in three ph	
	kW two phases split phase		
Manufacturer/supplier declaration - I certify on behalf of the company			

Power Quality. Harmonics. These tests should be carried out as specified in BS EN 61000-3-12. The relevant table applicable to the size of the **Generating Unit** should be completed. The chosen test should be undertaken with a fixed source of harmonics at two levels a) between 45 and 55% and b) at 100% of maximum export capacity.

The test should be carried out on a single **Generating Unit**. The results should be compared to the limits of table 2 of BS EN 61000-3-12 for single phase equipment, to table 3 of BS EN 61000-3-12 for three phase equipment or to table 1 of BS EN 61000-3-2 for equipment used.

Note that **Generating Units** meeting the requirements of BS EN 61000-3-12 may require further assessment with regards to harmonics. **Generating Units** with export capacity in excess of the limits laid down in BS EN 61000-3-12 may require the installation of a transformer with a rating of at least 4 times the rating of the **Generating Unit** in order to accept the connection to the network.

Generating Unit tested to BS EN 61000-3-2

Generator Unit rating per phase (rpp)		kW	
Harmonic	At 45-55% of rated output	100% of rated output	
	Measured Value MV in Amps	Measured Value MV in Amps	
2			
3			

11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

27					
28					
29					
30					
31					
32					
33					
34					
35					
36					

Generating Unit tested to BS EN 61000-3-12					
Generating Unit rating per phase (rpp)			kVA		Harmonic % (Amps) x 23 (kVA)
Harmonic	At 45-55% of rated output		100% of rated output		Limit in BS
	Measured Value MV in Amps	%	Measured Value MV in Amps	%	1 phase
2					
3					21
4					
5					

13					
THD					
PWHD					

--

--	--	--

--	--	--

--	--	--	--	--

--	--	--	--	--

--	--	--	--	--

--	--	--	--	--

--	--	--	--	--

--	--	--	--	--

--	--	--	--	--

--	--	--	--	--

--	--	--	--	--

--	--	--	--	--

61000-3-11					
Test Impedance	R		Ω	XI	
Standard Impedance	R	0.24 * 0.4 ^	Ω	XI	0.15 0.25
Maximum Impedance	R		Ω	XI	

* Applies to three phase and split single phase **Generating Units**

^ Applies to single phase **Generating Units** and **Generating Units** in a three phase system

For voltage change and flicker measurements the following formula is used to convert the measured values to the normalised values where the power factor of the output is 0.98 or above.

Normalised value = Measured value * reference source resistance / measured source resistance at test point

Single phase units reference source resistance is 0.4 Ω

Two phase units in a three phase system reference source resistance is 0.24 Ω

Two phase units in a split phase system reference source resistance is 0.4 Ω

Three phase units reference source resistance is 0.24 Ω

Where the power factor of the output is under 0.98 then the XI to R ratio should be close to that of the Standard Impedance.

The stopping test should be a trip from full load operation.

as % of rated AC current				
Limit	0.5%	0.5%	0.5%	

Power Quality. Power factor.				
	216.2V	230V	253V	Measured at full output. within $\pm 1.5\%$ the test.
Measured value				
Limit	>0.95	>0.95	>0.95	

Protection. Frequency tests					
Function	Setting		Trip test		"No t Freq /time
	Frequency	Time delay	Frequency	Time delay	
U/F stage 1	47.5Hz	20s			47.7H 25s
U/F stage 2	47Hz	0.5s			47.2H 19.98
					46.8H 0.48s
O/F stage 1	51.5Hz	90s			51.3H 95s
O/F stage 2	52Hz	0.5s			51.8H

be measured at a larger deviation than the minimum required to c
 No trip tests need to be carried out at the setting $\pm 4V$ and for the
 the table above to ensure that the protection will not trip in error.

Protection. Loss of Mains test.				
To be carried out at three output power levels with a tolerance of Power levels.				
Test Power	10%	55%	100%	10%
Balancing load on islanded network	95% of output	95% of output	95% of output	105% of output
Trip time. Limit is 0.5 seconds				
For Multi phase Micro-generators confirm that the device shuts down on removal of a single fuse as well as operation of all phases.				
Test Power	10%	55%	100%	10%
Balancing load on islanded network	95% of output	95% of output	95% of output	105% of output
Trip time. Ph1 fuse removed				
Test Power	10%	55%	100%	10%
Balancing load on islanded network	95% of output	95% of output	95% of output	105% of output
Trip time. Ph2 fuse removed				


	Start Frequency	Change	End Frequency
Positive Vector Shift	49.5Hz	+9 degrees	
Negative Vector Shift	50.5Hz	- 9 degrees	
Positive Frequency drift	49.5Hz	+0.19Hz/sec	51.5Hz
Negative Frequency drift	50.5Hz	-0.19Hz/sec	47.5Hz

Protection. Limited Frequency Sensitive Mode test				
Test sequence at power level >80%	Output power	Frequency	Prim	Sou
Step a)				
Step b)				
Step c)				
Step d)				
Step e)				
Step f)				
Step g)				
Test sequence at power level 40% - 60%	Output power	Frequency	Prim	Sou
Step a)				
Step b)				

Test b)			
Test c)			

Protection. Re-connection timer.					
Test should prove that the reconnection sequence starts after _____ seconds for restoration of voltage and frequency to within the stage					
Time delay setting	Measured delay		Checks on no reconnection is brought to just outside stage		
			At 266.2V	At 196.1V	At _____
Confirmation that the Generating Unit does not re-connect.					

Fault level contribution.					
For machines with electro-magnetic output			For Inverter output		
Parameter	Symbol	Value	Time after fault	Voltage	
Peak Short Circuit current	i_p		20ms		
Initial Value of aperiodic current	A		100ms		
Initial symmetrical short-circuit current*	I_k		250ms		



Appendix 6 Micro-generator and Generating Unit <50 kW 3 Confirmation

Micro-generator and Generating Unit <50 kW 3 phase D CONFIRMATION			
Generating Unit <50 kW 3 phase de-commissioning form and declar DNO by the Installer no later than 28 days after de-commissioning all Units in a Customer's Installation.			
To	ABC electricity distribution 99 West St, Imaginary Town, ZZ99 9AA	DNO or IDNC abcd@wxyz	
Electricity User at site			
User contact telephone			
Generating Unit Site address			
Post Code			
MPAN			
Generating Unit owner - if different from above			
Contact Address			
Contact telephone number			
Details of removed Generating Unit(s)			
Manufacturer and model type	Type Tested Reference number	Prime mover and fuel source	Phase

Appendix 7

Deliberately left blank

Appendix 8 Example calculations to determine if unequal generation across phases is acceptable or not.

A **Customer** installation might have 12kW of PV and a 3kW CHP. If the roof available the PV plant comprises 2 by 4.5kW inverters and a

A The following connection would be deemed acceptable

- Ph 1 4.5kW PV
- Ph 2 3kW PV plus 3kW CHP
- Ph 3 4.5kW PV

This would lead to

- 1.5kW imbalance with CHP at zero output
- 1.5kW imbalance with CHP and PV at maximum output
- 3kW imbalance with CHP at maximum output and PV at zero output

All of which are below the 16A imbalance limit.

B The following alternative connection for the same plant would be unacceptable

- Ph1 4.5kW PV plus 3kW CHP
- Ph 2 3kW PV

- Ph 3 5kW east roof 5kW west roof

B The following alternative connection for the same plan is unacceptable.

- Ph1 12kW east roof
- Ph2 5kW east roof 5kW west roof
- Ph 3 12kW west roof

This is not acceptable as Ph 1 would produce more than Ph 3 in the afternoon Ph 3 would produce more than Ph 1 in each case by a