

Dynamic FFR Excel Analysis Tool 2019 **User Guide**

Author: Honor Hynes

Customer Technical Policy

Date: 12/07/2019

Introduction

This User Guide describes how to use the 'NGESO FFR Dynamic Analysis Tool 2019' to assess pre-qualification test results as specified in FFR testing Guidance for Providers wishing to enter into a contract to provide Dynamic Firm Frequency Response. The following sections are included:

- Prepare Test Data
- Populate Excel Analysis Tool
- Analyse Results against pass criteria
- Test Report


Step	Action	Description	Examples
Prepar	re Test Data		
1	Format test data to be pasted into Tool.	Where applicable test data should be aggregated on a separate sheet to paste the total test volumes into the Tool.	Time Frequency (s) (Hz) Active Power (MW)
2	Overall response values should be copied into the Tool. e.g. Total aggregated data or, where baseline and measured power are provided, these need to be subtracted to provide a response value.	The Tool assumes that the response looks like generation i.e. Low frequency=generation increase. High frequency=generation decrease Check response values are +ve or -ve accordingly.	
Popula	ate Excel Analysis Tool		
3	General	Green cells can be edited. Pink cells are automatically populated. Formulae and tolerance bands assume test injections are identical to the published version. If not, timings/ ranges may need to be altered.	
4	Clear previous test data	In each Test data tab, delete the previous data from 'Frequency' and 'Active Power' columns.	
5	'Response' tab Copy contracted values into the green cells in 'response' tab. Check units are the same as raw data.	Units in this table should be the same as those in the measured test data. Note: High Frequency response values should be negative.	Frequency Deviation (Hz) Primary () Secondary () High () kW or MW? 0.1Hz 1.0 1.0 1.0 -1.0 -1.0 0.2Hz 2.0 2.0 2.0 -2.0 -2.0 0.3Hz 3.0 3.0 3.0 -3.0 -3.0 0.4Hz 4.0 4.0 4.0 -4.0 -4.0 0.5Hz 5.0 5.0 5.0 -5.0 -5.0

Step	Action	Description	Examples
	Drop down cell J7 and select correct units.	'Actual' response values will be automatically populated from Test 1 and 2 results.	
6	Pre-frequency change average: For Tests 1 and 2, to provide a reference from which to measure the response delivered, the average power is calculated for the 10 seconds before the frequency change.	Check/adjust the range to cover the 10s prior to the frequency change Cell I16 in Test 1 tabs, '=AVERAGE(C202:C301)' Cell F4 in Test 2 tabs '=AVERAGE(C22:C31)'	pre-Average 0.000000 (edit range to average 10s before frequency change)
7	Test 1.1, 1.2 Single Asset tabs Copy required data from raw file (check units correct)	These tabs should be used where there is a new asset or group of assets which will be assessed as part of an aggregated unit. These tabs can be duplicated and populated for several different assets as required.	Time (s) Frequency (Hz) Active Power (MW) 0 50 0.001 0.1 50 0.001 0.2 50 0.001
8	Test 1.1, 1.2 Single Asset tabs Edit Green Cells - Asset/s Name/Ref - Time Value at Which Frequency Changes	Primary and Secondary Start, and secondary end, or High start and end, times filled in automatically. Note: Default assumption that this asset can sustain maximum response for 30 minutes. If not the case, adjust cell adjust cell E17 'Secondary End' for Test 1.1 and E13 'High End' for Test 1,2 accordingly and clearly state in test report.	Asset/s Name/Ref NewVol1 Time Value at Which Frequency Changes NewVol1 Time Value at Which Frequency Changes 40 Time Value at Which Frequency Changes 30 Secondary Start High Start 60 High End 1829.9

50.1


49.9 (47) 49.8 49.7 49.6 49.6 49.5 49.4

			Dynamic FFR Analy
Step	Action	Description	Examples
9	Test 1.1, 1.2 Single Asset tabs The Tool calculates the response values shown by taking the <u>minimum</u> response value achieved for each timescale.	e.g Primary response = MINIMUM (from 10 to 30 seconds following start of 0.5Hz frequency step) minus (pre-average).	Primary Response 1.009 Secondary Response 1.009 -1.009
10	Test 1.1 and 1.2 Total Repeat Steps 6, 7 and 8	Used for the total test volume. In addition to the total Primary, Secondary and High frequency response values, this also calculates Standard Deviation over the 30 minute period and displays an additional close up graph to check that the total unit starts to respond within 2 seconds.	Test 1.1: Dynamic Delay Assessment Test 1.1: Dynamic Delay Assessment Test 1.1: Dynamic Delay Assessment Active Power (MW) Frequency (Hz) Frequency Change Test 1.1: Dynamic Delay Assessment Frequency (Hz) Frequency Change
11	Test 2.1 and 2.2 Enter data in the same way as for Test 1.	Note: All calculations and tolerance bands assume frequency injection aligns with the published version.	Time (s) Frequency (Hz) Active Power (MW) 0 50 0.00 1 50 0.00 2 50 0.00 3 50 0.00 4 50 0.00
			Test 2.1



Test 3
Copy required data from raw file.

Time (s)	Frequency (Hz)	Active Power (MW)
0.0	50.07	-0.01
1.0	50.07	-0.75
2.0	50.07	-0.76
3.0	50.07	-0.75
4.0	50.07	-0.78
5.0	50.07	-0.76
6.0	50.07	-0.74
7.0	50.07	-0.72
8.0	50.07	-0.69
9.0	50.06	-0.67
10.0	50.06	-0.64
11.0	50.06	-0.61
12.0	50.05	-0.58
13.0	50.05	-0.53
14.0	50.05	-0.50
15.0	50.05	-0.50




Description Examples Step Action Test 1.1 and 1.2 Total 17 Primary Response Minimum total response 5.046 achieved within each timescale can be found in the Test 1 Secondary 'total' tabs and will also High Response Response populate the 'Actual' values for 5.046 -5.046 0.5Hz frequency deviation in the 'Response' tab. quency Deviation (Hz) Actual ntracte Actual ntracted 0.1Hz 1.0 1.0 1.0 -1.0 -1.0 2.0 2.0 2.0 -2.0 -2.0 0.2Hz 0.3Hz 3.0 3.0 3.0 -3.0 -3.0 -4.0 0.4Hz 4.0 4.0 4.0 -4.0 -5.0 0.5Hz 5.0 5.0 5.0 5.0 -5.0 18 Test 1.1 and 1.2 Total Dynamic delay assessment graph For each test, alter the dynamic Check delay in response of active power due to a change delay graph so the x-axis shows a 2.00 50.4 (Z) 50.3 (A) in frequency is no greater than close up before and after the -3.00 50.2 frequency change point. 2 seconds. **9** -4.00 Frequency (Hz) — Frequency Change — — 2 Second Limit Shown in the Delay Assessment 19 Test 1.1 and 1.2 Total graph (Step 18). The Unit should progressively change to its maximum The unit should start to respond within 2 seconds and progress response monotonically towards its maximum response. Test 1.1 and 1.2 Total Standard deviation is assessed 20 SD 0.000534 from 10 seconds until 30 minutes Check that the standard % SD 0.011 after the frequency step, unless the deviation of load error at contracted values for primary and steady state over a 30 minute secondary are different. In this period does not exceed 2.5% case, standard deviation is of the maximum contracted assessed from 30 seconds until 30 active power response. minutes after the frequency step.

Step	Action	Description	Examples
		Note: SD calculation assumes Primary = Secondary.	
		If Primary ≠ Secondary then change cell J13 formula to =STDEV.P(INDIRECT(J9 &":"&J10))	


21 **Test 1.1 and 1.2 Total**

Check response is sustained for 30 minutes



22 Test 2.1 and 2.2

For Tests 2.1a and 2.2a check that a noticeable change in power in the correct direction is observed.



23 Test 2.1 and 2.2

See Step 12 for Test 2.1 and 2.2 b, c and d.

These values will populate the 'Response' tab

Check that minimum of the sampled values of active power within primary, secondary and high frequency

For each test the 'Actual' values are taken from the

(minimum value observed within Primary, Secondary or High Frequency response timescales) minus (Pre-frequency change average)

The error shown in the table opposite (from 'Response' tab) is a percentage of the expected

requency Deviation	n Primary ()			Secondary ()			High ()			
(Hz)	Tolerance	Contracte	Actual	Error %	Contracted	Actual	Error %	Contracted	Actual	Error %
0.1Hz	5%/-4%	1	1.00	-0.10	1	0.00	-100.00	-1	-1.00	0.02
0.2Hz	5%/-3%	2	2.00	0.05	2	0.00	-100.00	-2	-2.00	0.04
0.3Hz	5%/-2%	3	3.02	0.57	3	0.00	-100.00	-3	-3.02	0.40
0.4Hz	5%/-1%	4	4.03	0.82	4	0.00	-100.00	-4	-4.04	0.76
0.5Hz	5%/-0%	5	5.05	0.92	5	5.05	0.92	-5	-5.05	0.92

Step	Action	Description	Examples
	timescales are within the allowable tolerances.	response for that frequency deviation. = ('Actual'-'Contracted') / Actual'*100 Note: Secondary response is not assessed here for 0.1Hz- 0.4Hz frequency deviation.	
24	Test 2.1e and 2.2e Check that active power response is within the tolerances specified in Test Guidance.	If a small number of data samples fall outside the tolerance bands, this should be investigated and explained.	Test 2.1e: Frequency Sweep Test 50.8 4.00 4.00 50.4 50.4 50.4 50.4 50.2 6.00 49.8 49.8 49.6 49.6 Active Power (MW) Tolerance Tolerance Frequency (Hz)
25	Test 3 Check that active power response is consistent with the contracted performance within Primary, Secondary and/or High frequency response timescales.	The frequency axis has been reversed. Scale both vertical axes to be consistent with the total test volume. Once displayed this way, the active power can be clearly seen performing as expected. Inside the deadband, the active power response may move to zero. (There is no obligation to have a deadband. If the Unit does continue to respond within the deadband then it should respond proportionally with frequency.) Any unusual or unexpected performance should be investigated and explained. A re-test may be required.	Test 4: Variable Frequency Injection Test 130 140 150 150 150 150 150 150 15

Step	Action	Description	Examples	
Test R	eport			
26	Write report giving fe test results.	eedback on See report template		